

PHILIPPINE SPORTS COMMISSION

REQUEST FOR QUOTATION

The Philippine Sports Commission, through its Bids & Awards Committee, invites interested **PHILGEPS-accredited** suppliers to submit SEALED signed formal quotation/s for:

Particular	Quantity				ABC (PHP)	Place of Delivery
	Description	Qty	Unit	Total Cost		
Supply, Delivery and Installation of Wall Mounted Split Type Aircon Unit for COA Office	<p>1 Airconditioning Unit with Installation - ROOM 1 Branded, Inverter Wall Mounted/Split-Type Air-Conditioner (1 unit) Capacity: 2.5 HP, 24,000 btu/hr, 25,321 kj/hr, 220v, /60hz, R410a Gas-Cool only, GMCC Branded Compressor, EER: 14.0, Remote Control, Auto Start</p> <p>Installation Scope of Work: >High grade copper tubes standard thickness .28 >Rubber Insulation Using 1/2" thickness >Control Wire using Royal Cord #12 >Circuit Breaker with all weather box with THHN #10 Supply wire >with ACCU/Condenser support hanger/bracket using 2" x 2" x 3/16" with bolts & nut, dyna bolts. >Drain Line using 3/4"</p> <p>Materials Needed: >Copper Pipe, Size: 3/8 .28 - 40.0ft >Copper Pipe, Size: 5/8 .28 - 40.0ft >Rubber Insulation, Size: 3/8 x 1/2 - 40.0ft >Rubber Insulation, Size: 5/8 x 1/2 - 40.0ft >Poly Tape white 3" - 1 roll >Royal Cord #12 x 4, 3.0 meters (10.4ft x 4) - 1 length >Royal Cord #10 x 4, 3.0 meters (10.4 ft x 4) - 1 length >NEMA all weather circuit breaker with enclosure. 20 Amp. (Bolt-on) - 1 set >Floor Type Support Bracket with accessories & primer - 1 pc >Drain Pipe, PVC Blue - 3/4" - 1 pc >PVC Elbow - 2 pcs >Neltex Cement - 1 pint >Screw (FCU) size 8mm - 4 pcs >Bolts & Nuts - 4 sets (ACCU), Size: 3/16" x 1/2"</p>	1	lot		137,000.00	Property and Supplies Office, Rizal Memorial Sports Complex, P. Ocampo Sr. St. Malate, Manila
	<p>2 Airconditioning Unit with Installation - ROOM 2 Branded, Inverter Wall Mounted/Split-Type Air-Conditioner (1 unit) Capacity: 2.5 HP, 24,000 btu/hr, 25,321 kj/hr, 220v, /60hz, R410a Gas-Cool only, GMCC Branded Compressor, EER: 14.0, Remote Control, Auto Start</p> <p>Installation Scope of Work: >High grade copper tubes standard thickness .28 >Rubber Insulation Using 1/2" thickness</p>	1	lot			

>Control Wire using Royal Cord #12
 >Circuit Breaker with all weather box with THHN #10 Supply wire
 >with ACCU/Condenser support hanger/bracket using 2" x 2" x 3/16" with bolts & nut, dyna bolts.
 >Drain Line using 3/4"

Materials Needed:

>Copper Pipe, Size: 3/8 .28 - 40.0ft
 >Copper Pipe, Size: 5/8 .28 - 40.0ft
 >Rubber Insulation, Size: 3/8 x 1/2 - 40.0ft
 >Rubber Insulation, Size: 5/8 x 1/2 - 40.0ft
 >Poly Tape white 3" - 1 roll
 >Royal Cord #12 x 4, 3.0 meters (10.4ft x 4) - 1 length
 >Royal Cord #10 x 4, 3.0 meters (10.4 ft x 4) - 1 length
 >NEMA all weather circuit breaker with enclosure. 20 Amp. (Bolt-on) - 1 set
 >Floor Type Support Bracket with accessories & primer - 1 pc
 >Drain Pipe, PVC Blue - 3/4" - 1 pc
 >PVC Elbow - 2 pcs
 >Netex Cement - 1 pint
 >Screw (FCU) size 8mm - 4 pcs
 >Bolts & Nuts - 4 sets (ACCU), Size: 3/16" x 1/2"

NOTHING FOLLOWS

Terms of Delivery: 7 calendar day

The following documents must be submitted from May 11 - 15, 2018, 5:00 p.m. to the Office of Procurement located at 2nd floor, Administration Building, Rizal Memorial Sports Complex, Pablo Ocampo Sr. St. Malate Manila.

1. PHILGEPs Registration or PHILGEPs Certificate
2. ITR Form Year 2017 or Tax Clearance
3. Omnibus Sworn Statement (notarized)
4. Mayor's Permit

For additional information, please contact the Procurement Office nos. Telefax: 524-3512 or 524-4408 loc. 153/147.

The Commission reserves the right to not accept any and all quotations or not award the contract on the following grounds:

- There is prima facie evidence of collusion;
- The BAC failed to follow prescribed procurement procedures; and or
- There are justifiable grounds where the contract will not redound to the benefit of the government without incurring any liability to the affected bidder/s.


ATTY. GUILLERMO B. IROY, JR.
 BAC Chairman

Date Posted on PHILGEPs & PSC website: May 11, 2018

RFQ05022018