


|   |                                     |               |             |
|---|-------------------------------------|---------------|-------------|
|  | <b>PHILIPPINE SPORTS COMMISSION</b> | Page No.:     | Page 1 of 2 |
|   | <b>SCOPE OF WORK</b>                | Revision No.: | 0           |
|   | <b>PSC-SOP-VFMS-02 F05</b>          | Effectivity:  | 3-01-19     |


Name of Project: **REHABILITATION/RETROFITTING OF PHILIPPINE SPORTS COMPLEX OPEN BLEACHERS**

Location: **PHILSPORTS Complex, Meralco Ave. Pasig City**

Subject: **PROJECT SCOPE OF WORK**

This Scope of work is supplemental to the drawings but not limited to the following:

1. Mobilization of manpower and equipment.
2. Removal of all unwanted materials at ground floor.
3. Removal of all existing sanitary fixtures, plumbing fixtures and waterline fixtures.
4. Removal of all existing electrical roughing-ins; wiring materials, wiring fixtures, lighting fixtures and panel boards.
5. Removal of all existing doors and windows.
6. Demolition of concrete partition and chipping of all existing tiles at all comfort rooms.
7. Clearing and hauling of demolished materials.
8. Stripping of peeled-off paint.
9. Surface preparation and chipping works prior to retrofitting works.
10. Epoxy injection/mortar at slab and retaining wall.
11. Application of carbon fiber with epoxy.
12. Application of rust converter and protective covering paint.
13. Surface preparation prior to waterproofing works.
14. Correction of spailed and damaged bleachers prior to waterproofing.
15. Application of waterproofing at walls and bleachers.
16. Supply and installation of complete and brand-new electrical system including wiring, cables, conduits, panel boards, from the lighting fixture and wiring fixtures to the power supply.
17. Supply and installation of panel boards.
18. Supply and installation of waterline and new sewer line system.
19. Rehabilitation of drainage system.
20. Repainting of metal gate, ceiling, interior walls, columns, flooring, and baseboard.
21. Supply and installation of all lighting fixtures and receptacle outlets as indicated in the electrical plans.
22. Supply and installation of 30cm x 60cm glazed floor tiles (anti-slip) at stairs.
23. Supply and installation of 60cm x 60cm glazed floor tiles (anti-slip) at all comfort rooms.
24. Supply and installation of 30cm x 60cm wall tiles at all comfort rooms.
25. Installation of sanitary/plumbing fixtures.
26. Supply and installation of 12mm thk phenolic board toilet partition including stainless accessories at male and female comfort rooms/shower rooms.
27. Replacement of all existing wooden flush door including 2" x 5" jamb, lockset and hinges.
28. Supply and installation of ¼" thk frameless glass mirror with beveled sides and metal backplate at all comfort rooms.
29. Supply and installation of aluminum glass doors and aluminum glass partition.
30. Supply and installation of new feeder lines.
31. Supply and installation of grounding system.
32. Conduct insulation testing on all wires, cables, and panel boards.
33. Conduct ground resistance reading.
34. Testing and Commissioning.
35. Clearing, hauling and disposal of all debris.
36. Demobilization.

|   |                                     |               |             |
|---|-------------------------------------|---------------|-------------|
|  | <b>PHILIPPINE SPORTS COMMISSION</b> | Page No.:     | Page 2 of 2 |
|   | <b>SCOPE OF WORK</b>                | Revision No.: | 0           |
|   | <b>PSC-SOP-VFMS-02 F05</b>          | Effectivity:  | 3-01-19     |

Prepared by:

IRIS HAZEL ANNE C. LACORTE

Estimator

Date: \_\_\_\_\_

ENGR. KEVIN MARCH ADOR DIONISO

Engineer II

Date: \_\_\_\_\_

Checked/Reviewed by:

ENGR. PEDRO I. PINEDA, JR.

Head, Engineering & Maintenance Section

Date: \_\_\_\_\_

Recommending Approval:

DIR. MERLITA R. IBAY

OIC - Executive Director

Date: \_\_\_\_\_

Approved by:

HON. WILLIAM I. RAMIREZ

Chairman

Date: \_\_\_\_\_