	PHILIPPINE SPORTS COMMISSION	Page No.:	Page 1 of 2
	SCOPE OF WORK	Revision No.:	0
	PSC-SOP-VFMS-02 F05	Effectivity:	3-01-19

Name of Project: UPGRADING OF RMSC TRACK OVAL


Location: RMSC, P. Ocampo Sr. St., Malate, Manila

Date Prepared: February 13, 2019

Subject: PROJECT SCOPE OF WORK

This Scope of work is supplemental to the drawings but not limited to the following:

1. Mobilization of manpower and equipment.
2. Removal and replacement all of existing rubber at track, D-Sections.
3. Removal of damaged asphalt pavement at the track and D-Sections.
4. Base/Surface Preparations.
5. Supply and installation of Rubber Sandwich System.
6. Application of bituminous primer/tact coat.
7. Removal of existing embedded pole vault box discuss and hammer throw rings at D - Section.
8. Cover all cylinders of throwing cage at D – Section with concrete.
9. Repair concrete covers along the runway of steeple chase and insert pipes as water passages into the drainage.
10. Declogging and cleaning of internal and drainage of track oval.
11. Declogging and cleaning external drainage between track oval and bleachers.
12. Cleaning of Track and D-Sections areas prior to the spraying of bitumol.
13. Application of asphalt on Track and D-Sections.
14. Repair all damaged concrete retainer on sides of the track and in between D-Sections and Football Field.

	PHILIPPINE SPORTS COMMISSION	Page No.:	Page 2 of 2
	SCOPE OF WORK	Revision No.:	0
	PSC-SOP-VFMS-02 F05	Effectivity:	3-01-19

Prepared by:

OSCAR A. PAPELERA JR.

Engineer II

Date: _____

Checked/Reviewed by:

ENGR. PEDRO I. PINEDA, JR.

Head, Engineering & Maint. Section

Date: _____

Noted By:

MR. MANUEL G. BITOG

Acting Chief, Sports Facilities Division

Recommending Approval:

DIR. MERLITA R. IBAY

OIC, Office of the Executive Director

Date: _____

Approved by:

HON. WILLIAM I. RAMIREZ

Chairman

Date: _____